




# AUTO-TESTE VILLA, VIENNA E TREVI

Conforme combinado segue o procedimento de auto-teste da villa, Vienna e Trevi.

Desligar a máquina segurar os botão do café e o do vapor, ligar o botão geral, piscara então pode soltar os botão do café e o do vapor.

- Com a regulagem da agua do café no mínimo  
Botão de Vapor: sobe o grupo até ascender à luz do café.  
Botão de Café: aciona a bomba, com a torneira aberta sairá agua pelo tubo de vapor, com ela fechada e o grupo na de errogação irá sair pelo bico de café.  
\*Piscará a luz vermelha indicando pulsos do contador volumétrico.
- Com a regulagem da agua do café no meio  
Botão de Vapor: desce o grupo até tornar-se ascender à luz do café.  
Botão de Café: não tem função.
- Com a regulagem da agua do café no máximo  
Botão de Vapor: aciona o moinho.  
Botão de Café: aciona a bobina do dosador (dar apenas pulsos).

Segue tabela esquemática do modo de teste

Function	Button	Control setting	LED Indicator
Pump/Flow meter	Coffee		Fault LED (flow meter pulses) *
Brewing unit (Gearmotor) 	Steam Steam (Hot water)		Coffee LED Gear switch (brewing setting)
Heating	Coffee		
Brewing unit (Gearmotor) 	Steam Steam (Hot water)		Coffee LED Gear switch (home position)
Dosing magnet	Coffee		
Grinder	Steam (Hot water)		Steam LED Doser full
HWS microswitch			Steam LED